



ESTIMATE FOR PROPOSED PAINT & REPAIR WORKS ON EXTERIOR & INTERIOR OF PMO OFFICE , HALDWANI

S. No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs)
1.	<u>REPAIRS IN PLASTER :-</u> Exterior & Interior Repair & maintenance in plaster in 1:4 mortar including removal & disposal of old plaster, including application of two coats of URP mixed in proportionate part of cement, all including necessary shuttering/ scaffolding , with all labor, material & T&P etc complete.	1800	SFT		
2.	<u>PAINTING WORKS :-</u>				
a.	Interior Painting works on wall & Ceiling only on repaired areas The surface to be painted shall be prepared to the satisfaction of site-in-charge and shall be applied with two coats of primer, Two Coats of putty and touch up putty if required to achieve smooth finish. The surface to be painted with two coats of approved Oil Bond washable distemper of desired shade and color complete to the satisfaction of site-in-charge with all labor, material and T&P etc. complete.	1300	SFT		
b.	Exterior Painting- Providing and applying water proof exterior emulsion three coats of desired shade and color, a coat of touch up exterior wall putty complete with all labor, material and T&P etc and up to the satisfaction of site-in-charge.	21168	SFT		



3.	Miscellaneous works including water proofing & other allied works as & where required in the building including all labor, material & T&P.	- L.S -			
4.	Providing & fabricating tins shed structure in profile sheet 0.5 mm of desired shape & shades including insulation sheet below it, with necessary supporting system, trusses, purlins & all other M.S structural members & accessories etc complete.	1677.00	SFT		
	TOTAL AMOUNT				
For Mehta Consultants					